


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY  
T 26 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 25 & 26  
CORNER MONUMENT Set 1" X 36" pipe  
DATE MONUMENT PLACED AND WITNESSED 11-2-70  
WITNESSES TO CORNER..... 20" W. Pine N 89 W 38.1'



5" K. Pine N 70 E 58.7'  
(cor. plantation tree)  
C. Line of N-S blacktop Co. Rd DUE E 4'  
AND  
Cor. in 6'± fill section of County Road.

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. The corner was established on a straight line between Section corners to North and South and at a prorated distance to E. P. Waterman distances on the East side of Sec. 26. See old survey records at County Court House by E. P. Waterman, April 1894, L.1, P-405.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roer*  
REGISTERED LAND SURVEYOR 12028

DATE

11-9-70

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68