

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 9 W.	E-3; E-4
2. PROPERTY CONTROLLING IN SECTION 9	T. 26 N. R. 9 W.	2; 8; 11
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on March 11, 1980, established re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. ~~Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

	8		11		
Fd. 1/2" pipe & added RLS cap & set cedar post w/loc. tag			Fd. 1 1/2"x5' pipe & put ^{loc.} tag on corner fence post		
9" Maple N13°E	18.8		6" Oak S80°E	15.2	
6" Maple N11°W	27.0		4" Maple S26°E	18.3	
8" Maple S47°W	31.2		6" Oak S62°W	15.1	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 3 Schaaf pipe (Schaaf notes show he had orig. corner in 1933). Fd. & accepted in previous Dept. survey of 1969 & upgraded then.
- 4 Fd. & accepted gas pipe for W 1/4 Sec. 9. Corner used by Norton, Gourdie, Miller & Batzer, Inc. in 1965 survey & by RLS J. Nelson (Mich. Cons. Gas Co.) in 1977 survey.
- 2 Established 1/8 corner per standard B.L.M. instructions.
- 8 Fd. & accepted 1/2" pipe as established in 1965 survey by Norton, Gourdie, Miller & Batzer, Inc.; fence corner (fn. S & E) is 4'± W & 1'± N.
- 11 Fd. & accepted center of SW 1/4 of Sec. 9 as established by Norton, Gourdie, Miller & Batzer, Inc. in 1965 survey. Pipe is 1'± SE of corner fence post (fn. N & W).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	E-3		E-4		2	
Fd. brass cap on 1"x12" pipe inside 1 1/2"x48" pipe in creek			Fd. 2 1/2" gas pipe (2' above grade) & added cedar post w/loc. tag		Drove 5/8"x36" rerod w/RLS Cap & set ced.post w/loc. tag	
14" Cedar N30°E	20.31		*16" W. Pine N42°E	5.18	13" Cedar S24°W	22.6
12" Tamarack S55°E	49.42		*12" Oak N81°W	25.56	9" Cedar N12°W	39.1
14" Cedar S50°W	16.48		*10" W. Pine S39°W	38.09	6" Maple N50°E	25.1
16" Tamarack S88°W	34.23		*Wits. by RLS J. Nelson 1977			
Fd. ced.post Due N	33'					

SIGNED BY Carl F. Roser 5-8-80 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

GRAND TRAVERSE COUNTY
UNION TOWNSHIP

SURVEYOR'S MICHIGAN REGISTRATION NO. _____