

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 9 W.	G-5; H-3
2. PROPERTY CONTROLLING IN SECTION	9, T. 26 N. R. 9 W.	6; 9
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 28, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and of subsequent restoration:~~

C. (continued)

	9	
	Set 5/8"x36" rerod w/RLS Cap	
	& cedar post w/loc. tag.	
	6" Oak N78°E	25.8
	9" R. Pine S14°E	47.2
	12" Oak N89°W	51.3

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-5 Dept. monument set in 1971; replaced fd. Schaaf mon. (Schaaf notes, being a twp. map & legend in back of US field note book, indicate he had an orig. corner). Corner is in line with center of trail to north.

H-3 Fd. & accepted N 1/4 corner as set by Richards-Findorf-Richards in 1972 survey of Sec. 3. Corner is in north wheel track of E-W trail road.

6 Established center of NE 1/4 Sec. 9 per std. BLM instructions. (Drove rerod in cut-off 10" Maple stump.)

9 Set 1/8 corner per standard BLM instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5	H-3	6
Fd. Dept. monument (buried 0.7)	Fd. 5/8" rerod w/RLS cap	Set 5/8"x12" rerod w/RLS Cap
13" Oak N72°E 24.1	#12165 (buried 0.4')	& cedar post w/loc. tag.
12" Oak S65°E 55.4	18" Oak S41°W 14.9	8" Maple S68°W 34.0
12" Oak S13°W 47.2	7" Oak N47°W 55.6	6" Maple S68°E 21.3
10" Oak N45°W 50.3	16" Oak N28°E 16.5	5" Maple S03°E 35.2
Ced. post w/loc. tag	Set ced. post w/loc. tag	
Due S 33'	Due S 16.5	
Ctr. E-W Rd. Due S 3'±		


SIGNED BY Carl F. Roser DATE 5-8-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

GRAND TRAVERSE COUNTY
UNION TOWNSHIP