

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 9 W.	H-5; I-3; I-4; I-5
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above were, in a field survey on January 28, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by Decree of a Court of law:

A. ~~Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

I-5

Fd. Dept. Monument (buried 0.5),
 16" Oak S28°E 121.8
 6" J.Pine N70°E 46.4
 16" Oak N38°W 66.3
 Ced.post w/loc. tag S40°E 33'
 Ctr. N-S trl. road West 3'±
 Ctr. E-W road South 2'±
 Ctr. E-W gas pipeline North 120'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-5 Fd. & accepted Schaaf mon. His notes being a twp. map & legend in back of US field note book, indicate he had an orig. corner here. Corner is in approx. ctr. of E-W sand & gravel trail road.
- I-3 Fd. rerod for NE cor S-10 that fits wits. from Dept. survey (1959) of fd. 1½" pipe which was believed to perpetuate Gov. cor. as ident. & restored by E.H. Allyn in 1906.
- I-4 Fd. & accepted Schaaf mon for ¼ cor. Schaaf estab. ¼ cor by measurements from fd. orig. cors. ½ mile to N&S (1930's). Cor has also been used recently by others. Cor falls in approx. center of N-S two-track fire lane.
- I-5 Fd. dept. mon. (1971) which replaced fd. Schaaf mon. Schaaf notes being twp. map & legend in back of US field note book; indicate he had an original corner here.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p style="text-align: center;">H-5</p> <p>Fd. (Schaaf mon.) 1½" pipe in concrete.</p> <p>8" Cherry S75°W 62.2 5" W.Oak N46°E 78.4 11" W.Oak S62°E 142.6 Set cedar post w/loc. tag Due N 33'</p>	<p style="text-align: center;">I-3</p> <p>Fd. 5/8" rerod w/RLS cap; added 1"x3' pipe (bur. 0.6).</p> <p>10" Oak (trpl) S47°W 40.0 18" R.Pine N58°W 25.4 Ced.post w/loc. tag N45°W 33' Ctr. b-top rd. North 83'± Ctr. E-W trl.rd. So. 5'± in ¼ trl. rd. to South</p>	<p style="text-align: center;">I-4</p> <p>Fd. Schaaf mon., 1½" pipe in concrete (buried 0.3).</p> <p>7" W.Pine West 30.14 7" Oak S59°E 25.75 9" R.Pine S45°W 35.75 Set cedar post w/loc. tag Due E 16.5</p>
---	--	---

SIGNED BY Carl F. Roser 5-8-80 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

GRAND TRAVERSE COUNTY
UNION TOWNSHIP