

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---------------------------------------|------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 26 N. R. 9 W. | F-3; F-4; F-5 |
| 2. PROPERTY CONTROLLING IN SECTION 9 | T. 26 N. R. 9 W. | 7; 10 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. S. R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 28, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by Decree of a Court of law:

A - Description of original monument and accessories and/or subsequent restoration:

| C. (continued) | 7 | 10 |
|----------------|---|--|
| | Set 5/8"x36" rerod w/RLS cap & cedar post w/loc. tag. | Fd. 1 1/2" pipe, set cedar post w/loc. tag |
| | 8" Cedar S15°E 12.5 | 9" Maple S44°W 16.1 |
| | 9" Cedar N85°E 8.0 | 6" Cedar S80°E 31.4 |
| | 7" Cedar S53°W 12.3 | 9" Cedar N16°W 15.4 |
| | Creek 15' wide C W'ly Due S 18'± | |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-3 Reestablished N 1/4 corner on straight line & double over fd. 1/8 corner & fd. NW corner to W, per Norton, Gourdie, Miller & Batzer survey of 1965. Also fits 660 & 1320 fd. irons double over from N.
 - F-4 Set center of Sec. 9 at intersection of 1/4 lines.
 - F-5 Fd. & accepted conc. mon. for S 1/4 Sec. 9 as set by RLS P. Perla in 1965 survey for Sec. 16 & used by Mich. Cons. Gas Co. in subsequent surveys.
 - 7 Set 1/8 corner per standard BLM instructions.
 - 10 Fd. & accepted 1/8 corner as set by Norton, Gourdie, Miller & Batzer, Inc., in 1965 survey. Corner falls in old E-W fence. Also see E-5, SW corner of Sec. 9 (26-9)
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

| F-3 | F-4 | F-5 |
|---------------------------|--|---|
| Set DNR mon. & cedar post | Set 5/8"x36" rerod w/RLS Cap & cedar post w/loc. tag | Fd. conc. mon. added ced. post w/loc. tag |
| 5" Oak N68°W 41.3 | 12" Oak S45°E 14.1 | 7" Oak N81°W 24.62 |
| 13" W. Pine S80°W 87.1 | 10" R. Pine N81°E 28.5 | 6" W. Pine S14°W 11.4 |
| 12" Cedar S04°W 95.4 | 7" R. Pine N21°E 23.6 | 21" Oak S75°E 62.1 |
| | | 19" W. Pine N62°E 115.4 |
| | | Ctr. E-W Dirt rd. Due N 32'± |
| | | Fd. RR spk. in E-W Rd. N12°47'E 29.82 |


SIGNED BY Carl F. Roser DATE 5-8-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GRAND TRAVERSE COUNTY UNION TOWNSHIP