

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Grand Traverse (County)	Located In	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>10W</u>	MC $\frac{4}{9}$
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on November 5, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3						●							
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

MC $\frac{4}{9}$ – GLO – 49.71 CH over Lake – set Post for
 MC – L.S. Scranton – 1852
 W. Pine 20" N14°E 20 L.
 Hemlock 8" S80°E 16 L.
 - CSR – L. 2, P. 320 – E.P. Waterman - 1907
 Fd. Old pine stake & stumps at both Gov't. Wit.
 We drove new pine stake & made new Wit.
 N.P. 12" S15°E 9.7'
 Pine Stp. 24" N16°30'E 12.5'

DNR Cor. Rec. – 1963 – Fd. very old stake bottom in proper position from NE U.S. BT stump. Also evidence of older stake point below. Definitely a restoration of the original M.C.
 Set 1" pipe w/ 4" Brass Cap
 8" W. Oak N11°E 36.4'
 10" W. Pine Stp. N87½°E 19.0'
 Located 9.425 chain east of the ¼ corner between 4-9.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

MC $\frac{4}{9}$ – Meander Corner on line between Sec. 4 & 9 on E. side of Arm of Arbutus Lake being 621.74' East (640.86' – GLO) of ¼ corner – F3. Fd. 4" DOC (DNR) Brass Cap on 1" iron pipe per DNR record. Remains of both of Waterman's witnesses in place, the NE being GLO BT. West 23'+/- to edge of swamp – Lake level is way down. 4" DOC Mon. accepted as a careful & faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MC $\frac{4}{9}$ – 4" DOC (DNR) Brass Cap on 1" iron pipe.
 N 1' to set Orange Carsonite Post
 N10°E 36.70' to set N & T in W side 20" W. Oak (DNR)
 S52°E 36.32' to set N & T in SW side 5" W. Pine
 S84°W 15.94' to set N & T in E side 8" Birch
 N65°W 150.34' to set N & T in S side 14" W. Pine
 East 38.28' to set 2" Alum. Cap on 5/8" x 34" Rebar – SW Cor. of campground



Signed by: Craig W. McVean Date: 2/12/2002
 Surveyor's Michigan License No.: 39088