

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 10 W

DESCRIPTION OF CORNER Sec. corner common to Sections 19-20-30-29

CORNER MONUMENT Set Std. Dept. Mon

DATE MONUMENT PLACED AND WITNESSED 5-27-69

WITNESSES TO CORNER..... 15" W. Pine (triple) N 33 W 131.2'



18" Maple S 77 W 55.1'

Set Cedar Post & Tag Due N 33'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established at the position of a found shadow of dark soil where a pipe had set and Waterman's SW witness. The corner fits survey of Section 20 by E. H. Allyn, Nov. 1903, L.2-P 118; L.3-P234, and E. P. Waterman Survey, 1913 L.3-P.316.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roser*

DATE

6-27-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68