

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 10 W

DESCRIPTION OF CORNER Sec. corner common to Sections 29-30-31-32

CORNER MONUMENT Set Std. Dept. Mon. with Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 7-9-69

WITNESSES TO CORNER.....



13" R. Pine S 33 E 62.2'

13" R. Pine S 65 W 74.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set on average line of line fence to North which fits departure by single proportion E & W within less than 5 feet. The latitude of the corner was set by single proportion N, & S. ~~Single proportion~~ between section corners - one mile North and South.

SURVEYOR'S SEAL

SIGNED

*Carl F. Rose*

DATE

7-16-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR 2028

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68