

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 10 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 19 - 30

CORNER MONUMENT Set Std. Dept. Mon & 4" sq. top Cedar Post.

DATE MONUMENT PLACED AND WITNESSED 10-20-69

WITNESSES TO CORNER..... 24" Oak N 02 W 64.0'



18" W. Pine N 73 W 176.1'

Center E-W County Trail Road Due N 22'

AND
E-W Fence Remains Due S 5'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportion to U.S. dependent resurvey between section corners to E & W.

SURVEYOR'S SEAL

SIGNED

Carl F. Rose
REGISTERED LAND SURVEYOR 12028

DATE

10-27-69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68