

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 10 W
T 26 N R 11 W

DESCRIPTION OF CORNER Sec. corner common to Sections 19-30-24-25

CORNER MONUMENT Set Std. Dept. Mon & 4" sq. top Cedar post with location tag.

DATE MONUMENT PLACED AND WITNESSED 5-27-69

WITNESSES TO CORNER.....



6" Maple cluster N 30 E 83.0'

8" Maple, twin S 50 E 32.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set at proportionate distance between SW corner Section 30, and NW corner Sec. 19.

The corner is in line with very faint fence remains to the North.

Cor. is 30' South of Ctr. of E-W. Co. Trail Rd.

SURVEYOR'S SEAL

SIGNED

Carl F. Roer

DATE 6-3-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68