

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 10 W
T 25 N R 10 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 31 - 6

CORNER MONUMENT Set Std. Dept. Mon & 4" sq. top cedar post.

DATE MONUMENT PLACED AND WITNESSED 12-8-69

WITNESSES TO CORNER.....



40" Maple N 34 W 81.7'

18" Elm S 33 W 4.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a retracement survey in this area. The corner was established on a straight line between Section Corners to E & W and in line with an old fence N & S. This position fits very close to a single proportion distance E & W to US Dependent Resurvey (1852), and a survey of Section 31 by C. B. Tuller, July 1903, L 3, P.218, of old survey records at Register of Deeds Office. The corner falls near the base of a large popple tree in a group of cobble stones. Tuller notes call for elm stake surrounded by cobble stones.

SURVEYOR'S SEAL

SIGNED

Carl F. Roser

DATE 12-15-69

REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68