

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 26 N.R. 10 W


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER SEC. CORNER COMMON TO SECTIONS 13-14-23-24

CORNER MONUMENT Found Schaaf Monument. Replaced with Std. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED December 1968

WITNESSES TO CORNER.....



12" Oak N 45 W 69.0'

18" Oak S 55 W 93.6'

AND

Cedar Guard Post Due N. 33.0'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered from good Schaaf Pit, S 45 W, 34' and fair remains of Schaaf Pit, N45E, 34'. Schaaf notes show that he had an original corner here in 1933. The corner was recovered while making a survey in T26N-R0W.

SURVEYOR'S SEAL

SIGNED

*Carl F. Roer*

DATE 1/13/69

REGISTERED LAND SURVEYOR #12028