

MAR 16 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION
GRAND TRAVERSE
(County)

Located In: Corner Code =#

- 1. Public Land Survey T 26N R 11W A-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
GRAND TRAVERSE COUNTY
RECORDED
30 DEC 93 10:18 A.M.
KARON ANDERSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary G. Wilson, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9: Original Gov't Witnesses: 9" Beech, S45°E, 15 chains
15" Sugar, N60°E, 18 chains
Old post found by E.H. Allyn on June 26, 1905 (per Liber 2, Pg. 198).
December 27, 1980 (per Liber 3, Pg. 176).

Act 74 filed by R. Mitchell on

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9: No physical evidence of the original GLO witnesses were found.
Found iron pipe in monument box in centerline of County Road 633
2 ft., more or less, South of the centerline of Norton Road east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9: S.W. corner, Section 19
Perpetuated with 2-12" X 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.
N25°W 113.07' White Pine
N88°W 148.49' Power Pole
N45°E 52.83' Corner fence post
S45°E 49.15' Corner fence post
S60°E 72.0' 4" x 4" wood post
S71°E 108.68' 12" Ash

Corner approved by the Grand Traverse County Peer Review Group on 11-03-93.

Signed by Gary G. Wilson Date _____
Gary G. Wilson, PS
Surveyor's Michigan License No. 25881

