

MAR 16 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
GRAND TRAVERSE
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>11W</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
GRAND TRAVERSE COUNTY
RECORDED

30 DEC 93 10:18 A.M.

KARON ANDERSON
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary G. Wilson, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-9: N1/4 Cor., Sec. 30; Corner established in township subdivision by Alvin Austin Burt, US Deputy Surveyors (GLO), May 19, 1839; E.H. Allyn "restored old post to its original position - set cedar stake . . . Note: (N/14) corner is 19-1/2 feet North of straight line between (NE) & (NW) corners" in survey for Norton Road centerline, June 26, 1905, recorded in Liber 2 of County Surveyor Records, Page 198; Corner records under Act 74 by R.F. Mitchell, as a found 1/2" re-rod in centerline of Norton Road & on fence to South, Dec. 27, 1989, recorded in Liber 3 of Corners, on Page 180. (Per Act 74 by Donald A. Grier Jr., LS #33978 dated July 17, 1992 and recorded Liber 3, Pg. 368)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9: No physical evidence of the original GLO witnesses were found. Found 1/2" rod in monument box in the centerline of Norton Road on fence line South. Found concrete monument 19.5 feet North on front slope of ditch as described in Act 74 recorded in Liber 3, Pg. 368.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9: 1/4 corner common to Sections 19 & 30 Perpetuated with 2-1/2" x 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.

- S14°E 70.80' Power Pole
- N28°E 45.07' 14" Red Pine
- N45°E 50.98' 16" Red Pine
- South 52.55' 1/2" Re-rod
- S30°W 22.91' Pavement Box in centerline Norton Road

Corner approved by the Grand Traverse County Peer Review Group on 11-03-93.

Signed by Gary G. Wilson
Gary G. Wilson, PS
Surveyor's Michigan License No. 25881

Date December 28, 1993

