

REMONUMENTATION

LIBER 1103 ... 690

MAY 07 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Grand Traverse Located In: Corner Code #  
(County)

1. Public Land Survey T 26 N R 11 W E-03  
G.T. County Code 96-29

I, Corey J. Hughes, in a field survey performed in October, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner point mentioned in lines 1 and 2 above was in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

Glo 1838 Burt set post  
Sugar 14 N35E 18 and Beech 11 S68W 35

E.P. Waterman 1913 found stone, Elm 12 N52E 51.8' and Sugar 5 S46 1/4 E 48'.

P. R. Stout 1981 found bolt in pavement box.  
PP S43W 69.18'; PP N70W 79.73'; PP N49E 76.5'

J. F. Korr Jr. 1986 found bolt in pavement box and Stout witnesses.

MDOT 1993 found Iron in pavement box and Stout witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found bolt in pavement box in CL over broken pavement box 1.3' down and over cobble stones 2.3' down in old road bed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Replaced existing evidence with re-mon monument and pavement box.  
PK in PP Az 44° 81.52'  
PK in PP Az 107° 171.95'  
PK in PP Az 222° 81.02'  
Nail in PP Az 320° 76.30'

STATE OF MICHIGAN  
GRAND TRAVERSE COUNTY  
FILED  
27 DEC 96 2:24 P.M.  
KARON ANDERSON  
REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

UNANIMOUSLY ACCEPTED BY THE  
GRAND TRAVERSE COUNTY PEER  
REVIEW GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC  
ACT 345 OF 1990 AT A MEETING  
HELD ON 9-27-96

*Robert F. Mitchell*  
ROBERT F. MITCHELL, P.S., CHAIRMAN



Corner approved by the Grand Traverse County Peer Review Group on September 24, 1996

Signed by Corey J. Hughes Date 12.23.96  
Corey J. Hughes Michigan P.S. license No. 20706