

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 11 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 25-36

CORNER MONUMENT Set Std. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 5-28-69

WITNESSES TO CORNER..... 9" Maple N 13 W 72.8'



10" Twin Elm S 38 E 40.1'

Set Cedar Post & Tag Due S 33'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established at the position of a found shadow of dark soil circle where pipe had been set and from Hemlock witness North by E. P. Waterman 1907. Liber 2, P 278-279, Section 36, County Survey Records. Corner falls in the approximate center of E-W trail roads.

SURVEYOR'S SEAL

SIGNED

Carl F. Boez
REGISTERED LAND SURVEYOR 12028

DATE

6-3-69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68