


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY  
T 26 N R 11 W

DESCRIPTION OF CORNER E 1/16 corner common to Sections 25 - 36  
CORNER MONUMENT Set 5/8" x 12" Galv. Sq. Hd. Bolt, buried 3"  
DATE MONUMENT PLACED AND WITNESSED 1-16-70  
WITNESSES TO CORNER..... 12" W. Pine & Forestry Tag S 58 W 59.7'



6" W. Pine N 50 W 57.0'  
Approx Ctr. Irregular) Due S 6'  
AND E-W Trail Road )

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set equidistant between the N 1/4 corner and the NE corner of Section 36. The corner fits very closely a survey of Section 36 by E.P. Waterman May 1907, L.2-P.278 of County Surveyors records at Register of Deeds Office. The corner is in line with fence remains South.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Carl F. Roer*  
REGISTERED LAND SURVEYOR 12028

DATE

1-23-70

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68