

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 11 W.	L-9; M-9
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on FEBRUARY 3, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-9 FOUND 1 1/4" PIPE AND DROVE 5/8" REROD (BURIED) IN OLD IMPASSABLE E-W ROAD GRADE WEST -DRIVABLE ROAD EAST.
- M-9 EXISTING DEPT. MONUMENT AS ESTABLISHED IN 1969 RETRACEMENT SURVEY; PROJECT NO. 69-6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9	M-9
FD 1 1/4" PIPE & DROVE 5/8"	FD DEPT MON & CEDAR POST W/LOC TAG
X 36" REROD W/RLS CAP INSIDE	*10" MAPLE CLUSTER N30°E 83.0
PIPE & SET CEDAR POST W/LOC TAG	*18" MAPLE STUMP S50°E 32.6
11" MAPLE N30°E 34.92	CTR OF E-W GRAVEL RD NORTH 30'
10" MAPLE N45°W 29.73	5" R. PINE S30°E 48.2
11" MAPLE S26°E 17.70	10"R. PINE S20°W 62.3
CTR OF OLD E-W RD GRADE NORTH 6'±	

* = 1969 DEPT. WITS.

SIGNED BY Carl F. Roser 06/02/83 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ BLAIR TWP.
GRAND TRAVERSE COUNTY