

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 26 N. R. 11 W.	M-7; M-6
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on FEBRUARY 3, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-7 DEPT MON AT POSITION OF FD 3/4" PIPE BY OLD COR FN POST PER DEPT SURVEY, T26N-R10W, PROJECT #69-6; DATED 1968-1969. FITS E.H. ALLYN SURVEY IN 1903; LIBER 3, PG 234 OF CO. SURVEYOR RECORDS.
- M-6 FD CONC MON FOR 1/4 COR COMM TO SEC'S 13(26-11) AND SEC 18(26-10) AS RECOVERED BY RLS'S BILL BATZER AND WALT FRASER PER E.H. ALLYN SURVEY 1903 AND E.P. WATERMAN SURVEY 1905.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>M-7</u>	<u>M-7</u>
FD DEPT MON & CEDAR POST	FD CONC MON W/REROD & CAP #13026 &
14" Y. BIRCH S43°W 15.0	SET CEDAR POST W/LOC TAG
25" HEMLOCK S74°W 28.1	**SW COR GARAGE N60°E 33.1
3" HEMLOCK N70°E 27.00	** 6" ASPEN STP EAST 16.28
	** 5" BALSAM S64°E 23.00
	CTR OF E-W B-TOP RD SOUTH 46'±
	CTR OF TOP OF (N END) of
	18" CONC CULVERT S10°W 16.9

SIGNED BY Carl F. Roser 06/02/83 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ BLAIR TWP.
GRAND TRAVERSE COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET