

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>26</u> N. S., R. <u>11</u> E. W.	<u>6, 9</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JANUARY 14, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 6 FD AND ACCEPTED 1/2" REROD BY RLS, BOB MITCHELL, FOR NW COR OF SE 1/4 OF NE 1/4 OF SEC 14. COR FALLS IN OLD N-S FN REMAINS. A COR FN POST (DOWN) WITH FN REMAINS E-W-S IS NORTH, 23.5'±.
- 9 ESTAB SW COR OF SE 1/4 OF NE 1/4 OF SEC 14 PER STD B.L.M. DIRECTIONS. COR FALLS AT EAST EDGE OF OLD IRREG N-S LOGGING RD GRADE DOWN STEEP HILL TO NORTH. AN OLD N-S FN (MOSTLY DOWN) WITH SOUTH END FN POST IS S57°E, 17.6'±.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p style="text-align: center;">6</p> FD 1/2" REROD W/RLS CAP #28417 & CED POST. ADDED LOC TAG TO POST. 7" CEDAR N65°E 1.45' 4" CEDAR N86°W 8.73' 8" CEDAR S56°E 15.53' 6" CEDAR N42°W 12.26'	<p style="text-align: center;">9</p> DROVE 5/8" X 34" REROD W/RLS CAP & SET CED POST W/LOC TAG. 10" MAPLE S04°E 9.0' 11" MAPLE N44°W 16.7' 5" TW MAPLE N14°E 4.6'
--	--

SIGNED BY Carl F. Roser 02-11-85 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BLAIR TWP.
GRAND TRAVERSE COUNTY