

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 12 W.
T. 27 NR. 12 W.

Grand Traverse COUNTY

DESCRIPTION OF CORNER Meander Corner common to Sections 6 and 31
located 11.78 ch. west of SE corner Sec. 31

DESCRIPTION OF CORNER MONUMENT 1"x24" pipe

WITNESSES TO CORNER

10" Twin Oak - N56W - 47 links
8" Poplar - S51W - 34 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Set corner on the calculated true town line at west edge of floodings to identify the town line and to witness the section corners east, which were not set because of flood water.

Corner was placed and witnessed June 16, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Billing* DATE 6/29/59
REGISTERED LAND SURVEYOR