

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 26 N R 12 W

DESCRIPTION OF CORNER 32, T26N, R12W
M.C. common to Secs: 5, T25N, R12W

CORNER MONUMENT Set 4"x4" conc. filled pipe w/brass cap.

DATE MONUMENT PLACED AND WITNESSED 1965 Shadko

WITNESSES TO CORNER..... Cedar 6" N 03-30 E 28.60'



Cedar 8" N 40-30 W 28.45'

Maple 10" S 61-30 W 11.28'

AND

Maple 6" S 37-00 W 28.10'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set on Section line 68.4' Westerly from old found pipe by C.P. Tuller set for U.S. M.C. about 1910.

(Old M.C. falls in lake bottom water 1 1/2'± deep. Shoreline has been eroded about 40'±).

NOTE: A complete survey history will be found in G.A. Shadko Field Book #39 and in his P.F.S. files for Bass Lake & GreenLake, Grand Trav. Co.

SURVEYOR'S SEAL

SIGNED

Carl F. Roaver
REGISTERED LAND SURVEYOR

DATE

June 1971

DISTRIBUTION:

12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68