

MAR 16 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Whitewater Twp.

Grand Traverse (County) Located In: Sec. 29 Corner Code C-9

1. Public Land Survey	T <u>27N</u> R <u>9W</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
GRAND TRAVERSE COUNTY  
RECORDED

29 DEC 93 3:04 P.M.  
KARON ANDERSON  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Corey J. Hughes, in a field survey on December 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9) Section cor common to 19, 20, 29 & 30 T27N, R9W, set post by US Survey May 1850 witnesses are W.Pine, 22" S78°W - 64 lks and y.pine 17"-N70°E-28 lks; DNR survey July 1968 by Ken Ostling, set cons. dept. Monument from U.S.B.T. stumps both in place, the NE with partial face, good original corner. Buried DNR Schaaf corner with new monument, 8" w.oak-N46°E-6.2', 7" w.oak-S50°E-41.0 ft., 9" w.oak-S53°W-40.8 ft.; corner recording Liber 2, Pg. 568 by D.F. Delamater, 4" oak-N45°W-49.36 ft., 5" oak-S75°W-17.33 ft., 5" oak-S30°E-18.12 ft., 12" oak-N45°E-6.03 ft., fd DNR monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9) Section corner common to 19, 20, 29 & 30, T27N, R9W, fd DNR monument with (1" pipe) cap broken off, also found Schaaf corner below, found all witnesses intact from D.F. Delamater corner recording and a cedar post adjacent to corner, and is accepted as a careful and faithful perpetuation of the position of the original corner.

Remonumented this position with a 2 1/2" x 30" flanged bottom galvanized iron pipe with 3/4" brass cap stamped Grand Traverse County Remonumentation.

Corner found is a direct perpetuation of the G.L.O. Survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9) Section corner common to sections 19, 20, 29 & 30, T27N, R9W.

- 2 1/2" x 30" flanged bottom galvanized iron pipe with 3/4" brass cap, stamped Grand Traverse County Remonumentation
- 4" oak - N40°W - 49.36 Ft. fd spike
- 12" oak - N52°E - 6.03 ft. fd spike
- 6" oak - S08°E - 18.12 ft. fd spike
- 6" oak - S79°W - 17.32 ft. fd spike

Corner approved by Grand Traverse County Peer Review Group on October 6, 1993

Signed by Corey J. Hughes Date December 28, 1993

Surveyor's Michigan License No. 20706

