

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Grand Traverse (County)	Located In	Corner Code #
1. Public Land Survey	T <u>27N</u> R <u>9W</u>	<u>H5</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 10, 1999 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| <p><u>H5</u>- 1850- L. Lyon, GLO, Set Beech Post
 Sugar 12" N70°E 20 Links Sugar 10" S53°W 36 Links
 - L.1, pg. 28-29 - W. Slawson - 1874-Sec. 10 survey
 - L.2, pg. 340 - 1907- E. P. Waterman- Fnd. Stone and ¼ post
 Placed Stone with 'X' on top and added '1907'
 on S side of new stone. Placed new stone where old stake
 and small blue stone used to be.
 - L.8, pg. 336 - C.O. Carver - 1930 - stone with 'X'</p> | <p>- 1967- P. Perla, Consumers Power Co.
 Stone with 'X' found.
 20" Elm N20°31'W 83.85' 24" Maple N48°02'W 53.29'
 6" Maple N76°52'W 69.50'
 - LCRC L.3 , pg.351- 1991- R. Mitchell- Found Stone with 'X'
 per Slawson, Waterman & Carver.
 S60°W 61.46' 6" Jack Pine S40°E 37.85' Power Pole
 N55°W 53.27' 36" Maple N82°W 42.30' Oak</p> |
|---|---|

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

H5- ¼ corner common to sections 10 and 15. - Found 1.2' X 0.7' X 1.0' Granite Stone with 'X' on top and '1907' on S. side with a ring of stone per LCRC. Stone in island of gravel & sand road 'T' intersection - N, S. & E. Stone with 'X' by Waterman at apparent Slawson perpetuation accepted as a careful & faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H5- Replaced stone with 'X' with 3 ¼ " 'Grand Traverse Co. Remon.' brass cap on 2 ½ " X 30 " galvanized iron pipe in a ring of stone
 Place stone with 'X' inverted at N. base of pipe as memorial.
 S36°E 37.85' to set N&T in SW side Power Pole (RM)
 South 32.98' to fnd. ½" Capped Iron Rod #23514
 S7°W 34.02' to set N&T in E. side 6" R. Pine scribed 'XBT'
 S76°W 59.50' to set N&T in S. side 10" R. Oak scribed 'XBT'
 N80°W 42.30' to set N&T in N side 10" R. Oak (RM)
 N50°W 53.21' to set N&T in N side 26" S. Maple (CPC, RM)



Signed by: Craig W. McVean Date: 12/13/1999
 Surveyor's Michigan License No.: 39088