

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:

Grand Traverse  
(County)

Located In

Corner Code #

- |                                      |         |         |         |  |             |
|--------------------------------------|---------|---------|---------|--|-------------|
| 1. Public Land Survey                |         | T _____ | R _____ |  |             |
|                                      |         | T _____ | R _____ |  |             |
| 2. Property Controlling in Section   | S 17    | T 27N   | R 9W    |  | NW-NW 1/64  |
|                                      | S 17    | T 27N   | R 9W    |  | C-W-NW 1/64 |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ |  |             |
|                                      | S _____ | T _____ | R _____ |  |             |

Register of Deeds Stamp & File Number

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on January 11, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

NW-NW 1/64 - None

C-W-NW 1/64 - None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

NW-NW 1/64 - Being NE Cor. of SW 1/4 of NW 1/4 of NW 1/4 of Sec. 17 T27N R9W - set 2" Alum. Cap on 5/8" x 34" Rebar per Standard BLM procedure.

C-W-NW 1/64 - Being the SE Cor. Of the SW 1/4 of NW 1/4 of NW 1/4 of Sec. 17 T27N R9W - set 2" Alum. Cap on 5/8" x 34" Rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NW-NW 1/64 - 2" AC on 5/8" x 34" Rebar  
 NE 1' to set Blue Carsonite Post w/ Loc. Tag  
 N44°W 28.65' to N & T NE side 11" R. Oak  
 N38°E 3.29' to N & T in SE side 5" Sco. Pine  
 S45°E 12.99' to N & T in SW side 4" Sco. Pine  
 S15°W 13.81' to N & T in W side 6" Sco. Pine

C-W-NW 1/64 - 2" AC on 5/8" x 34" Rebar  
 NE 1' to set Blue Carsonite Post w/ Loc. Tag  
 N7°W 7.47' to N & t in E side 13" Tw. R. Maple  
 N65°E 24.42' to N & T in NW side 5" R. Oak  
 S71°E 27.64' to N & T in N side 6" W. Pine  
 S46°W 14.48' to N & T in SE side 3" R. Oak

Signed by:

Craig W. McVean

Date:

1/22/2001

Surveyor's Michigan License No.:

39088