

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Grand Traverse Located In _____ Corner Code # _____
 (County)

- | | | | | |
|--------------------------------------|-------------|--------------|-------------|----------|
| 1. Public Land Survey | T _____ | R _____ | | |
| | T _____ | R _____ | | |
| 2. Property Controlling in Section | S <u>10</u> | T <u>27N</u> | R <u>9W</u> | <u>4</u> |
| | S <u>10</u> | T <u>27N</u> | R <u>9W</u> | <u>8</u> |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | |
| | S _____ | T _____ | R _____ | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on May 10, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 4 - Unrec. Survey- Mitchell and Assoc. #951448 - 1996-iron set 8 -None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

- | | |
|---|--|
| <p><u>4</u> - NW 1/16, Sec. 10, T27N, R9W
 Fnd. RFM 1/2" Capped Rebar # 28417-30079
 N-S 2-track is 82± W. 1/2" CIR is accepted as the best available evidence of the position of the corner.</p> | <p><u>8</u> - C-W 1/16, Sec. 10, T27N, R9W
 Set 2" Alum. cap on 5/8" x 34" Rebar per standard BLM procedure. Single strand barb wire to S. is 12' W. CL. of E-Wly gravel rd. is 43± N.</p> |
|---|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <p><u>4</u> - Replaced 1/2" X 18" CIR w/ 2" Alum. Cap on 5/8" x 34" Rebar
 N0°E 39.05' to N&T in E. side 6" W. Pine
 S87°E 16.49' to N&T in N. side 3" W. Pine
 S16°E 13.49' to N&T in E. side 2" W. Pine
 S38°W 17.10' to N&T in NW side 23" R. Oak
 Set Blue Carsonite Post w/ loc. tag 1' NE</p> | <p><u>8</u> - 2" AC on 5/8" x 34" Rebar w/ ring of cobbles.
 N35°E 115.78' to set N&T in SE side 8" W. Pine
 N18°W 114.64' to set N&T in NE side 11" W. Pine
 N85°W 118.11' to set N&T in S. side 12" B. Cherry
 S42°W 83.92' to set N&T in SE side 6" W. Pine
 Set Blue Carsonite Post w/ loc. tag 1' NW</p> |
|---|---|

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 1/22/2001