

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Grand Traverse (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	S 22 T 27N R 9W 13 S 22 T 27N R 9W 16	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on March 13, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9								●					
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

13 -None

16 -CSR- L. 2, P. 446- E.P. Waterman- 1912-Stake

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

13 - SE 1/16, Sec. 22, T27N, R9W
Set 2" Alum. Cap on 5/8" x 34" Rebar per Standard BLM Procedure.

16 - E. 1/16 corner common to Sec 22 & 27, T27N, R9W
No evidence of Waterman's stake fnd. Set 4" x 36" Concrete Mon. with 1/2" Iron Rod per Standard BLM Procedure in E-W firelane. CL of E-W Firelane is 3' S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13 - 2" AC on 5/8" x 34" Rebar
S40°W 20.91' to N&T in SW side 3" W. Pine
N36°W 17.12' to N&T in NE side 4" W. Pine
N28°E 25.01' to N&T in NW side 8" W. Oak
S32°E 14.14' to N&T in NE side 13" W. Oak
Set Blue Carsonite Post w/ loc. tag 1' NW

16 - 4" x 36" Concrete Mon. with 1/2" Iron Rod
N54°W 40.24' to N&T in SW side 8" W. Oak
S35°W 30.49' to N&T in SE side 11" W. Pine
S40°E 54.89' to N&T in NE side 6" R. Pine
North 33.00' to Set 2" AC on 5/8" x 34" Rebar on line with
Blue Carsonite Post w/ loc. tag.

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 1/22/2001

