

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N. R. 10 W⁹


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER Sec. corner common to sections 19-30 24-25

CORNER MONUMENT 8/20/68 Set Std. Dept. Monument & Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 8/20/68

WITNESSES TO CORNER.....



<u>12" W. Pine</u>	<u>N 17 E</u>	<u>11.3'</u>
<u>10" R. Pine</u>	<u>S 33 E</u>	<u>31.4'</u>
<u>30" W. Pine</u>	<u>Due S</u>	<u>32.9'</u>
<u>Random East</u>	<u>Due N.</u>	<u>128'</u>

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found as a 1½" pipe with Schaaf pits. Schaaf notes show he had an original corner here. Corner has been used and witnessed recently by others. Replaced 1½" pipe with Std. Dept. Mon.

SURVEYOR'S SEAL

SIGNED

Carl F. Rosen

DATE

9/16/68

REGISTERED LAND SURVEYOR #12028