

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 9 W


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER 1/4 CORNER COMMON TO SECTIONS 21 & 28

CORNER MONUMENT SET STD. DEPT. MON IN APPROXIMATE CENTER OF E-W FIRE LANE TRAIL

DATE MONUMENT PLACED AND WITNESSED 7/5/68

WITNESSES TO CORNER.....



| | | |
|------------------|--------|-------|
| 6" Twin Oak | N 32 W | 9.3' |
| 5" Twin Oak | N 65 E | 23.6' |
| 6" Twin Oak | S 72 E | 37.3' |
| AND | | |
| Cedar Guard Post | Due N | 9' |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by data from "Waterman" survey of Sec. 21, dated Sept. 1915, in L.2-P.499 at Deed Office, County Court House. He set the corner from one USBT (SW) of which a part of the stump is still standing (W. Pine Stump, S 62 W, 36').

SURVEYOR'S SEAL

SIGNED Carl F. Joser DATE 9/16/68
REGISTERED LAND SURVEYOR #12028