

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 27 ^{N.} R. 9 ^{W.}	A-3; B-3; B-5
2. PROPERTY CONTROLLING IN SECTION 7	T. 27 ^{N.} R. 9 ^{W.}	10
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ ^{N.} S. R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 30, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

10

Set 3/4"x30" Pipe & cedar post
w/loc. tag

20" Twin Oak	S22°E	7.5
7" W. Pine	S74°W	32.9
5" W. Pine	N89°E	16.3

S 1/16 on E line Sec. 12 T27N-R10W
N00°06'W 17.75

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
-3 Sec. corner common to Sec. 6 & 7 on W line of T27N-R9W. Reestablished corner at record distance S of found NE corner of Sec. 12 (27-10) per previous surveys of record by EP Waterman; Liber 2, pg.424, Nov. 1911; Liber 1, pg.519 & Liber 10, pg.132 April-May 1915; Liber 4, pg. 275 & Liber 10, pg.23 1916. This agrees with 1852 government resurvey.

-3 Fd. old 1 1/4" pipe (deep) & raised with 1"x20" iron rod per EP Waterman survey of Sec. 7, dated 1916, Liber 10, page 23.

-5 Fd. 3/4" pipe at old fence corner, fences N-S-W; per survey of Sec. 7 by EP Waterman, dated 1916, Liber 10, page 23.

10 Fd. 3/4" iron rod in old N-S fence & added 3/4"x30" pipe per Waterman survey of Sec. 7, dated 1916, Liber 10, page 23.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3	B-3	B-5
Set DNR Mon. & Cedar Post	1"x20" Iron Rod over 1 1/4" pipe	Fd. 3/4" pipe & set DNR MON. & Cedar Post
6" Oak N89°E 124.3	30" Oak S85°W 46.70	6" R. Pine S68°E 8.0
PK Nail in side of PP (angle pt. in highline) S45°E 68.05	7" Oak N73°W 41.81	14" Maple S37°W 22.7
Cor. common to Sec. 1 & 12 T27N-R10W N00°06'W 75.24	6" Maple N41°W 65.37	5" R. Pine N48°W 11.1
	3" R. Pine N68°E 52.33	
	Set ced.post w/loc. tag	
	Due W 33'	

SIGNED BY Carl F. Roser 4-28-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GRAND TRAVERSE COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET

