

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27</u> ^{N.} _• , R. <u>9</u> ^{W.}	<u>I-9; K-8; K-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ ^{N.} _{S.} , R. _____ ^{E.} _{W.}	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} _{S.} , R. _____ ^{E.} _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 6-19- 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- I-9 Fd. 1" pipe & Y. Pine witness stump NE per survey by E.P. Waterman. See Liber 2, Pg 447 Grand Traverse County Surveyor Records at Register of Deeds.
 - K-8 Reestablished corner at proportionate distance and on line between SE S=23 and comp. position for NE S-23 in Roots Lake per Perla Survey for Consumers Power Company.
 - K-9 Restored corner in center of fire lanes N-S-E-W, which fits corner position by double proportion reasonably close.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9	K-8	K-9
Fd. 1" pipe & Cedar Gd. Post	Set DNR mon & Cedar Gd. Post	Set DNR Monument
4" R. Pine S38W 95.0'	18" W. Pine N29E 81.0'	12" R. Pine S49W 41.0'
9" Oak S23E 76.6'	9" R. Pine N70E 29.6'	14" W. Pine N22E 36.5'
9" Oak N70E 55.9'	7" R. Pine S81E 41.6'	12" R. Pine S26E 36.8'
Ctrln. N-S Co Rd Due W 16'	C.Line N-S fire	Set Ced. post w/loc
Ctrln. fire in E-W Due S 9'	lane Due E 8'	tag N45W 33'

SIGNED BY Carl F. Roser DATE 7-16-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____