

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T 27 N. R. 9 W.	M-3, L-3, K-2	
2. PROPERTY CONTROLLING IN SECTION	T 27 N. R. 9 W.	14	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 9, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. Continued:

K-2  
Fd. 3/4" Pipe (buried)  
26" Maple S10°W 50.41  
24" Maple S70°W 22.63  
P. Pole Due N 44.43

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 14 Fd. 1 1/2" pipe for 1/8 cor that fits E.P. Waterman survey of Sec. 1 dated Aug. 1909.
- M-3 Dept. cor. (1967)-as monumented at position of stk., stone and two wit. remains per E.P. Waterman survey of Sec. 1 dated Aug. 1909.
- L-3 Fd. & accepted 5/8" bolt w/nut for S1/4 cor. of Sec. 1. Fits E.P. Waterman's Wit., Pine stump 28, S11°E, 43' & fits recovered 1/8 cor. & Sec. cor. to E. per E.P.W.'s survey & Sec. Sub'n of Sec. 1, dated Aug. 1909. Cor. also fits line across fd. N1/4 cor. & ctr. of Sec. 1 per E.P.W. survey. A newer homemade conc. mon. (origin unknown) is N47°29'E, 5.7' from our accepted E.P.W. 1/4 cor. Also about 8.2'S of homemade conc. mon. is a white ced. post that is within one foot of fitting E.H. Allyn 1904 Wit; Allyn's actual cor. not in evidence.
- K-2 Fd. 3/4" pipe (buried) w/remains of old bucket around it. Fits two 1909 E.P. Waterman Wits.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	14	M-3	L-3
Fd. 1 1/2" pipe & added ced. post w/loc tag.	Fd. DNR mon. added ced. post	Fd. 5/8" threaded bolt & repl. w/DNR mon. & ced. post	
6" W. Pine S75°E 19.8	*12" Maple S50°W 10.6	5" Ironwood N75°E 11.65	
7" W. Pine S35°E 38.1	*12" Maple N15°E 15.5	10" Cherry(twin) S55°E 13.49	
7" W. Pine S85°W 27.8	*11" Maple S70°E 19.8	8" Maple S05°E 22.78	
	*=Old Wits	Ctr. line of NWly-SEly rd. is North 55'±	
		Fd. Rd. conc. mon. N70°E 5.63	

SIGNED BY Carl F. Roser DATE 01-21-82


SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ GRAND TRAVERSE COUNTY