

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY:	T. 27 N. R. 9 W.	L-2, L-1, M-2
2. PROPERTY CONTROLLING IN SECTION	1, T. 27 N. R. 9 W.	7
3. MISCELLANEOUS PROPERTY IN SECTION	_____ T. _____ N. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 9, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

**C. Continued:**

- M-2
- Fd. DNR mon. & added ced. post.
  - \*14" Maple (cluster) N65°E 37.8
  - \*13" Maple S50°W 30.7
  - 6" Oak S25°W 21.5
  - Fd. rd. conc. mon. (flush)
  - East 1.70
  - \*=Old Wits.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- L-2 Accepted fd. old rd. conc. mon. for ctr. of Sec. 1. Fits within less than one foot from computed position of intersection of 1/4 lines. Cor. falls near easterly edge of old overgrown N-S skid trail & in line with vague fence remains to East.
  - L-1 Fd. & accepted rd. conc. mon. for N1/4 cor. of Sec. 1. Previously used & wit. by RLS, Glen DeLamater and fits survey & Sec. Sub'n by E.P. Waterman dated Aug. 1909.
  - 7 Estab. N1/8 cor. on East line of Sec. 1 at prorated dist. to G.L.O. plat. (NE cor. of S1/2 of frl. NE1/4 of Sec. 1). Cor falls in boiling springs at base of hill.
  - M-2 Dept. cor. (1967)-as monumented at position of old ced. fn. post remains (3'deep) per E.P. Waterman survey of Sec. 1 dated Aug. 1909.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-2	L-1	7
Fd. Rd. Conc. mon. & added ced. post w/loc. tag.	Fd. Rd. conc. mon. (buried 0.4) in road.	Drove ced. post in spring for 1/8 cor.
15" oak N35°E 30.7	*Rerod w/RLS cap #13030 North 32.92	Set * & ced. post N89°59'28"W on 1/8 line 89.19'.
14" oak N05°W 25.0	*15" Tw. Ash N15°E 49.20	Set * & ced. post S00°00'06"W on Sec. line 77.10'.
8" Maple N80°W 23.3	*40" Maple N20°E 67.60	Set * & ced. post N00°00'06"E on Sec. line 97.70' in power line opening.
Ctr. of High Line North 182'±	*24" Maple N75°E 25.90	*=5/8" x 36" rerod w/plastic RLS cap
	Ctr. E-W gravel rd. S 3'±	
	*=Old Wits	

SIGNED BY Carl F. Roser DATE 01-21-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ GRAND TRAVERSE COUNTY