

APR 26 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
For corners in  
Grand Traverse  
(County)

Located In: Corner Code =#

1. Public Land Survey	T	27N	R	10W	G-5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
GRAND TRAVERSE COUNTY  
RECORDED

29 DEC 95 9:53 A.M.

KARON ANDERSON  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Gary G. Wilson December 21 1995

I, Gary G. Wilson, in a field survey on December 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5 Corner common to Sections 9, 10, 15 & 16  
County Surveyor records: E. P. Waterman found fence post with remains of both U.S. Gov't witnesses in May 1906. In July 1923, Carver located corner by references to the Government witness stumps. In May 1946, Sawyer found remains of corner and set stake & tack.

In June 1960, Gourdie/Fraser survey references a found axel shaft. In 1971, Gourdie/Fraser survey refers to found iron and concrete monument set as Southeast corner of plat of Hunting Woods.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Corner common to Sections 9, 10, 15 & 16  
Found concrete monument at Southeast corner of plat of Hunting Woods.

Accepted as a careful and faithful reestablishment of the position of the original corner.

UNANIMOUSLY ACCEPTED BY THE  
GRAND TRAVERSE COUNTY PEER  
REVIEW GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC  
ACT 345 OF 1990 AT A MEETING  
HELD ON 12-11-95  
RFM  
ROBERT F. MITCHELL, P.S., Chairman



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 Corner common to Sections 9, 10, 15 & 16  
Perpetuated with 2-1/2" x 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.

- N70°E 19.50' 8" Red Pine
- S27°E 21.59' 8" Red Pine
- S25°W 36.24' 10" Red Oak
- S82°W 38.65' 8" Red Pine

Corner approved by the Grand Traverse County Peer Review Group on December 11, 1995.

Signed by Gary G. Wilson  
Surveyor's Michigan License No. 25881

Date 12-27-95