

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 27 N R 10 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 35 & 36

CORNER MONUMENT Found 1 1/2" Well point with Single strand wire & posts running
S & W from Well Point. Set location tag on Cor. fence post.

DATE MONUMENT PLACED AND WITNESSED 5-6-70

WITNESSES TO CORNER..... _____



9" R. Pine N 67 E 81.7'

18" Oak S 20 E 70.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered while making a retracement survey in this area. The corner as found and occupied fits within less than 10 feet of the computed position of a corner by single proportion. Accepted the 1 1/2" Well Point as best evidence of true corner. There was no conclusive evidence of USBT remains.

SURVEYOR'S SEAL

SIGNED

Carl F. Roser

DATE

6/16/70

DISTRIBUTION:

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68