

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

GRAND TRAVERSE COUNTY


T 27 N R 10 W

DESCRIPTION OF CORNER Sec. corner common to Sections 25-26-35-36

CORNER MONUMENT Set Std. Dept. Monument & Cedar Guard Post.

DATE MONUMENT PLACED AND WITNESSED 5-5-70

WITNESSES TO CORNER..... _____



14" Oak N 26 W 27.3'

16" Oak S 48 E 11.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a retracement survey in this area. The corner was set by double proportion between found Section corners one mile E & W and found 1/4 corners one-half mile N & S. No evidence of USBT remains.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Carl F. Roer

DATE

6-16-70

REGISTERED LAND SURVEYOR 12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68