

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 27 N. R. 10 W. <input checked="" type="radio"/>	M-7
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. 27 N. R. 10 W. <input checked="" type="radio"/>	9; 15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W. <input type="radio"/>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 16, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 M-7 Sec. corner common to Sec. 18 & 19 (27-9) & 13 & 24 (27-10). Recovered 1 1/4" short pipe in concrete block (Schaaf mon.). Schaaf notes (1930's) in dept. US field notes indicate he had an original govt. cor. from two USBT stumps. Perla also fd. this corner & used it in 1967 in survey for Consumers Power Co. C.P.Tuller had this corner in 1889 from USBT's. Both USBT (pine stumps) SW are still standing.

9 Recovered definite stake bottom shadow per Waterman Sec. 14 subdivision dated Dec. 1907.

15 Established 1/16 corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7	9	15
Fd. Schaaf conc. mon. & added DNR mon. & ced.post w/loc.tag	Fd. stk.bottom shadow & set 1 1/4"x42" pipe & ced.post w/loc. tag	Set 1"x36" pipe & cedar post w/loc. tag
8" W. Pine N69°W 49.2	Cor.P.Pole (#x29) N80°E 68.80	10" Oak N20°E 22.5
7" Oak N29°E 10.45	12" Oak N36°E 47.9	4" R. Pine N65°E 51.8
6" Oak S67°E 9.18	10" Oak N02°E 68.0	8" R. Pine S18°E 60.4
4" W. Pine S35°W 7.80	9" W. Pine N35°W 71.3	6" Maple N40°W 44.6

SIGNED BY Carl F. Roser 4-28-77 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ GRAND TRAVERSE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET