

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 27 <sup>N.</sup> <input checked="" type="radio"/> , R. 10 <sup>W.</sup> <input checked="" type="radio"/>	M-6
2. PROPERTY CONTROLLING IN SECTION 14 _____	T. 27 <sup>N.</sup> <input checked="" type="radio"/> , R. 10 <sup>W.</sup> <input checked="" type="radio"/>	1; 3; 4
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> <input type="radio"/> , R. _____ <sup>E.</sup> <input type="radio"/> <sub><sup>S.</sup> <input type="radio"/>, <sup>W.</sup> <input type="radio"/></sub>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 10, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (CONTINUED)

4

Set 3/4"x36" pipe-cedar post  
w/loc. tag

6" Oak	N34°E	25.0
9" R. Pine	N79°E	18.1
7" Oak	S58°E	24.0
10" Oak	S69°W	28.5

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-6 Found definite pointed stake bottom from remains of 3 definite pine stump witnesses as noted by E.P. Waterman in Sept. 1917, Liber 3, page 381, old co. surveyors record at Reg. of Deeds. Fits recovered 1/16 corner & center of section to E. Tuller also had same corner from original USBT's date 1889.
- 1 Restored 1/16 corner from witness by E.P. Waterman date 1907 (W.P. stp. W 1.6').
  - 3 Found concrete monument in place by R.L.S. Walt Fraser.
  - 4 Established center of NW¼ of Section 14 per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6	1	3
Set DNR mon. w/cedar post	Set 1"x36" pipe-cedar post w/loc. tag	Fd. Conc. Mon. & put tag on new large corner fence post
11" R. Pine S23°E 12.6	6" Oak N13°E 45.7	4" W. Pine N08°E 42.20
12" R. Pine S41°W 30.6	9" Oak N46°E 29.2	8" Maple N82°E 66.60
10" W. Pine N50°W 22.9	5" Oak S09°E 33.3	5" R. Pine S64°E 110.55
7" R. Pine Due N 18.5	10" Oak S79°W 23.5	
N-S Trv. Due W 61.0	Old 26" W. Pine Stp. Wit.	
E-W Random Due N 9.5	Due W 1.6	

SIGNED BY Carl F. Roser 4-28-77 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ GRAND TRAVERSE COUNTY