

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 27 N. R. 10 W. ●	L-5
2. PROPERTY CONTROLLING IN SECTION 12	T. 27 N. R. 10 W. ●	2; 8
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 31, 1976, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5 Recovered govt. corner (1852) per C.P.Tuller survey Sec. 13 dated 1889 & E.P.Waterman survey of Sec. 13 dated 1917 & his survey of Sec. 12 dated 1911. All of above listed surveys had govt. corner from U.S.B.T.'s. We fd. shadow of stk. bottom from Tuller 1889 witness & Waterman 1911 witness, N. Pine (stump) N54°E 22'. We removed the dept. monument set in error in 1966. This dept. mon. was located S14°02'W 8.2' from proper govt. corner.
- 2 Found 1" iron pipe buried in E'ly edge of gravel county road; pipe fits Co. Rd. Comm. witnesses. Pipe also fits survey of N line of NE¼ of Sec. 12 by Waterman dated 1911.
- 8 Established W 1/16 on E-W ¼ line, equidistant & on line between W¼ & ctr. of Sec. 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5	2	8
Set DNR mon. & cedar post	Fd. 1" pipe (buried)	Drove 3/4"x30" pipe & cedar post w/loc. tag
16" Oak S42°E 16.4	Power Pole S74°W 71.10	7" R. Pine S12°E 16.8
10" R. Pine S63°W 27.7	Power Pole S42°E 34.00	5" Oak S65°E 9.2
4" W. Pine N41°W 17.7	Power Pole N25°E 70.50	6" Oak N37°W 25.5
5" Oak N79°E 33.4	Set cedar post w/loc. tag	5" Oak N31°E 26.5
	Due E 33'	

SIGNED BY Carl F. Roser 4-28-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ GRAND TRAVERSE COUNTY