

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|---|----------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>27</u> N. <u>•</u> , R. <u>10</u> W. <u>•</u> | <u>I-9; I-8; J-8</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>23</u> | T. <u>27</u> N. <u>•</u> , R. <u>10</u> W. <u>•</u> | <u>7</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____, R. _____ E. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 28, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

XX

C. Continued:

| | J-8 | | 7 | | |
|---|-------|--|--|------|--|
| Set 5/8" x 36" re-rod w/R.L.S. cap & ced. post w/loc. tag | | | Set 5/8" x 36" re-rod w/R.L.S. cap & ced. post w/loc. tag. | | |
| 18" Red Pine S40°W | 78.09 | | 7" Red Pine N87°E | 14.2 | |
| 3" White Pine S28°E | 27.14 | | 8" Oak N27°W | 37.4 | |
| 11" Cherry (twin) N84°E | 32.53 | | 7" Oak S52°E | 17.4 | |
| Ctr of E-W trail, North | 115'± | | | | |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-9 Fd. 5/8" re-rod that fits Czubak survey of S.W.1/4 of Sec. 23.
- I-8 Fd. Sq. Conc. Mon. that fits Cert. Surveys in this area.
- J-8 Established ctr. of Sec. 23 at intersection of one-quarter lines.
- 7 Established 1/8 cor. per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | I-9 | | I-8 | | |
|------------------------------------|-------|--|--|-------|--|
| Fd. 5/8" re-rod (buried in b. top) | | | Fd. Sq. Conc. Mon. added loc. tag to cor. fn. post | | |
| P. Pole N58°E | 38.60 | | * P. Pole S35°E | 64.05 | |
| * 17" Oak N48°W | 133.0 | | 11" Oak N55°E | 74.34 | |
| Re-rod w/cap #13030 East | 32.93 | | 4" Oak S85°W | 32.09 | |
| In ctr. line of B.T. Rd. N-S-W | | | Ctr. Power Line South | 50'± | |
| *=Old Wits | | | Fn. Cor. (S & W) West | 2'± | |

*=Old Wits.

SIGNED BY Carl F. Roser 6-05-81 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

T27N - R10W
GRAND TRAVERSE COUNTY