

MAR 16 1994

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Long Lake Twp.

Grand Traverse (County) Located In: Sec. 4 Corner Code #G-2

1. Public Land Survey T 27N R 12W \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
 GRAND TRAVERSE COUNTY  
 RECORDED  
 29 DEC 93 3:01 P.M.  
 KAREN ANDERSON  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Corey J. Hughes, in a field survey on December 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2) 1/4 cor. common to Sections 3 & 4, T27N, R12W - U.S. resurvey July 31, 1851, 1/4 post, Beech 6" for corner, Elm 14" S80°W 21 LKS; county surveyor Peter G. Perla, iron in mon. box fd, 1972, P Pole west 66.65', 14" Elm east 42.21' & 12" Elm S.W. 250.31', Rec Act 132 Liber 1 Page 330; G.T. Co. Rd. Comm., date unknown, P Pole N87°W 66.60', Elm S85°E 42.21' & 4" pine S39°E 44.96'; Russell L. Roon MDOT, fd 1" iron in mon. box in C/L of Tilton Rd., 1984, P.P. N80°W 66.73', 6" R Pine (north tree) S82°E 34.60', 9" R Pine (5th tree) S45°E 44.98' & 8" R Pine (11th tree) S20°E 75.63', Rec Act 74 Liber 2 Pg 587.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2) 1/4 corner common to Sections 3 & 4, T27N, R12W - fd iron pipe in mon. box with 3/4" iron pipe found in 2nd road grade 24" below surface and is accepted as a careful and faithful perpetuation of the position of the original corner.  
 Remonumented this position with a 2 1/2" x 30" flanged-bottom galvanized iron pipe with a 3 1/4" brass cap stamped "Grand Traverse County Remonumentation".  
 Replaced broken monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2) 1/4 cor. common to Sections 3 & 4, T27N, R12W - 2 1/2" x 30" flanged-bottom galvanized iron pipe w/ a 3 1/4" brass cap stamped "Grand Traverse County Remonumentation", inside monument box  
 Found P-K nail in N face of P pole west 66.75'  
 Found spike in N face of 8" R Pine S84°E 34.55'  
 Found spike in S.W. face of 12" R Pine S48°E 44.92'  
 Found D.H. Nail & MDOT washer in N.E. face of 10" R Pine S26°E 75.61'

Corner approved by Grand Traverse County Peer Review Group on Nov. 3, 1993.

Signed by Corey J. Hughes *Corey J. Hughes* Date December 28, 1993  
 Surveyor's Michigan License No. 20706

