

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27. NR. 12 W.

Grand Traverse COUNTY

DESCRIPTION OF CORNER South 1/4 corner of Section 31

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

Notch in 20" W. Pine - N51W - 31½ links

14" R. Pine - N60E - 53 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey in this area. Could find no evidence of government Bts. Corner falls about 1 chain west of road on old RR grade and just south of E-W rut road.

North 1/4 corner of Section 6, T26NR12W is 1.47 chains east.

Corner was placed and witnessed June 15, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Collins* DATE 6/30/59
REGISTERED LAND SURVEYOR