

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 NR 12 W

Grand Traverse COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 31 and 32

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

24" W. Pine stump - N14E - 23 1/2 links

9" B. Oak - S70E- 94 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey in this area. Good corner 1/2 mile north, calculated corner 1/2 mile south. No evidence of government BTs.

Corner was placed and witnessed 6/15/59

SURVEYORS SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 6/30/59