

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 27. NR. 12 W.

Grand Traverse COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 29-30-31-32

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

20" R. Oak	-	N17W	-	29½ links
8" Maple	-	N39E	-	84½ links
10" R. Oak	-	S56E	-	136½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found good stake bottom at corner, which I conclude to be Tullers of 1903, at which time he could identify the government BT. Tuller's NW pine stump witness in place, and roots in road NE for government BT site. Checks Tuller's distance north to recovered 1/8 corner between 29 and 30.

Corner was placed and witnessed June 15, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR DATE 6/30/59-