

✓
MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 12 W


GRAND TRAVERSE COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 19-30

CORNER MONUMENT Set 5' of 1" pipe in muck area; and squared cedar guard post.

DATE MONUMENT PLACED AND WITNESSED 2/7/68

WITNESSES TO CORNER.....



5" Tamarack S 70 W 3.8'

8" Tamarack Due S 20.3'

AND

Cor. is 2.8' S of E-W Random Line

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by single proportion between section corner to east and west. The corner fit the calls in the GLO notes for a small lake and hemlock ridge very close when consideration was given to the fact that the GLO calls were taken on a random line.

SURVEYOR'S SEAL

SIGNED

Paul F. Reser
REGISTERED LAND SURVEYOR #12028

DATE

7/17/68