

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27 N. R. 12 W.	C-4, D-5
2. PROPERTY CONTROLLING IN SECTION 8	T. 27 N. R. 12 W.	10
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-12, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-4 RECOVERED 2" PIPE AS ESTAB IN 1919 BY E.P.WATERMAN; S.P. TO U.S. BIT NW OF SEC 8 AND U.S.M.C. AT N END OF CEDAR LAKE ON W LINE OF SEC 8. SEE CO SURVEY REC'S, L.10, P.53. COR ALSO RECOVERED AND USED BY SEVERAL RLS'S IN SUBDIVISION OF SEC 8.
- 10 FD OLD 1/2" PIPE WITH 3/8" SPK INSIDE FOR NW COR OF FRL SW 1/4 OF FRL SW 1/4 OF SEC 8. E.P. WATERMAN SET A PIPE HERE IN 1919; L.10,P.53. COR HAS SINCE BEEN USED BY SEVERAL RLS'S TO SUBDIVIDE SEC 8.
- D-5 FD 3" IRON (ENGINE VALVE) FOR S 1/4 COR OF SEC 8. COR RECOVERED BY WM B BATZER DURING SURVEY TO SUBDIVIDE SEC 8. COR ALSO USED BY RLS'S L.CZUBEK AND GOURDIE-FRASER IN SEC 8 SUBDIVISIONS. COR FITS OLD OCCUPANCY, RD ROW'S & OLD LINE FN TO WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4	10	D-5
FD 2" IR PIPE IN N-S GRAVEL RD.	FD 3/8" SPK INSIDE OLD	FD 3" IR (ENGINE VALVE) & SET
*22" W PINE S78°W 24.44	1/2" PIPE.	CED POST W/LOC TAG.
*14" W PINE S54°E 53.84	30" OAK S54°E 23.31	12" R PINE N20°E 97.55
*40" W PINE N18°E 59.32	16" OAK N54°W 118.60	*28" MAPLE N20°W 19.73
P. POLE N75°W 56.45	12" OAK N26°E 51.27	*33" MAPLE S84°W 14.05
SET CED POST	SET CED	10" W PINE S24°E 82.62
W/LOC TAG. WEST 33'	POST W/	**PREVIOUS SURVEY WITS BY
**PREVIOUS SUR WIT BY WM B. BATZER.	LOC TAG SOUTH 33'	WM B. BATZER.

SIGNED BY Carl F. Roser 01-30-85 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

LONG LAKE TWP.
GRAND TRAVERSE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____