

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W.	11 U.S.M.C. 2476.7' W OF D-5
2. PROPERTY CONTROLLING IN SECTION 8, T. 27 N., R. 12	N. S., R. 12 E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____	N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on DECEMBER 12, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**B. (CONTINUED)**

~~Description of original monument and accessories and/or subsequent restoration~~

11 FD 3/8" REROD W/PLASTIC RLS CAP #13026 (WM B BATZER) FOR NE COR OF FRL SW 1/4 OF FRL SW 1/4 OF SEC 8 (CTR OF FRL SW 1/4 OF S-8). USED BY BATZER AND ALSO CZUBEK IN SUB'N OF N 1/2 OF FRL SW 1/4 OF SEC 8.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

\*RECOVERED U.S.-G.L.O. (RESURVEY - 1850) MEANDER COR ON S LINE OF SEC 8 AT E LINE OF CEDAR LAKE. FD HOLLOW 10"± CED STUMP SHOWING PARTIAL FACE WITH SCRIBES AND U.S.B.T. CED (STUMP) SE EXACT. U.S. LINE NOTES READ N88°37'W CORRECTED BETW SEC'S 8 & 17 AT 77.48 CH TO E SIDE OF LAKE, CEDAR 4" MEANDER COR; CED 8" S75°E 37 LINKS (FD- NOW 24"± & REMARKED 50± YEARS AGO); CED 12" N65°E 40 LINKS (PUSHED OUT AND LYING NEAR LAKE SHORE TO WEST). CUT OUT BACK SIDE OF HOLLOW LEANING U.S.M.C. STUMP (LEFT FACE) AND DROVE 1 1/4" BY 5 1/2" PIPE IN CTR WITH 1" X 36" PIPE INSIDE (CRIMPED) ON TOP & RIVETED DNR ALUM CAP ON TOP (ABOUT 1' ABOVE GRD). OLD E-W FN REMAINS (ALL DOWN) RUNNING E ARE 8'± N AT LAKE IN CED SWAMP (HILL TO E).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

DROVE DNR MON INSIDE HOLLOW U.S.M.C. (CED STUMP) & DROVE STL FN POST.	11
5" CEDAR N45°E 13.3	FD 3/8" REROD W/RLS CAP #13026 & SET CED POST W/LOG TAG.
9" TW MAPL N60°E 36.0	3" W PINE S15°E 26.27
6" CEDAR S65°E 22.1	5" W PINE S06°W 43.64
5" CEDAR S30°E 7.2	7" W PINE S48°W 41.80
WATERS' EDGE WEST 9'±	NARROW WINDING E-W GRAVEL CO RD IS 20'± N. SET ST FN POST 33'- SO FOR SOUTHERLY R.O.W. LINE.

SIGNED BY Carl F. Roser 01-30-85 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)  
LONG LAKE TWP.  
GRAND TRAVERSE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_