

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	
2. PROPERTY CONTROLLING IN SECTION <u>8</u>	T. <u>27</u> N. S., R. <u>12</u> E. W.	*U.S.M.C. 2095.83' S OF C-4. <u>15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-12, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- * RESTORED U.S.M.C. ON W LINE OF SEC 8 AT NORTH SIDE OF CEDAR LAKE AT PRORATED DISTANCE & ON LINE ACROSS FD 1/8 COR & 1/4 COR TO NORTH; PER E.P. WATERMAN 1919 SUR WHO HAD ORIG GLO (RESURVEY) U.S.M.C. SEE LIBER 10, PG 53 OF OLD CO SURVEYOR RECORDS AT REG OF DEEDS. MON CONSISTS OF 1" X 34" PIPE INSIDE 1 1/4" X 36" PIPE (TOTAL LTH 5 1/2') & RIVETED DNR ALUM CAP ON TOP.
- 15 DROVE 5/8" X 34" REROD FOR SE COR OF FRL SW 1/4 OF FRL SW 1/4 OF SEC 8; AT PRORATED DISTANCE & ON LINE BETW FD U.S.M.C. TO WEST AND 1/4 COR TO EAST. INTERSEC OF OLD FN'S E-W-N (COULD NOT FIND COR POST) IS N70°54'W, 30.3'±.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

		15		
DROVE DNR MON & STEEL FN POST.			DROVE 5/8" X 34" REROD W/RLS CAP. &	
8" TAMARACK	N66°E	33.4'	SET CED POST W/LOC TAG.	
10" CEDAR	N04°E	41.2'	14" R PINE	S54°W 58.1'
9" CEDAR	N20°W	33.9'	32" MAPLE	N40°W 20.5'
DROVE 5/8" X 34" REROD W/RLS CAP & SET FN POST.			7" OAK	S20°E 1.8'
	N01°05'25"E	129.63		

SIGNED BY Carl F. Roser 01-30-85 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

LONG LAKE TWP.
GRAND TRAVERSE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____