

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27 N. R. 12 W.	K-13, J-13
2. PROPERTY CONTROLLING IN SECTION	35, T. 27 N. R. 12 W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on FEBRUARY 1, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-13 FD. 3/4" PIPE FOR STD. CORNER BETW SEC'S. 35 & 36 ON SOUTH LINE OF T27N, R12W. COR. FITS PRIOR SURVEY'S NOTED IN OLD COUNTY SURVEYORS REC. AT REG. OF DEEDS OFFICE: E.P.WATERMAN, L.2, P.458, APR. 1914 AND A.G.ERICKSON, L.2, P.513, NOV. 1957.

J-13 FD. CONC. MON. FOR S1/4 OF SEC. 35.

16 DROVE 5/8" X 36" RE-ROD FOR SE COR. OF W1/2-SE1/4 OF SEC. 35, EQUI-DISTANT & ON LINE BETW THE SE COR. & S1/4 COR. OF SEC. 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13	J-13	16
FD. 3/4" PIPE; REPL W/D.N.R. MON. & CED. POST.	FD. CONC. MON; ADDED CED. POST	SET 5/8"X36" RE-ROD W/RLS CAP & CED. POST W/LOC TAG
15" OAK N5°W 6.43	19" W. PINE N20°W 3.05	6" OAK N25°W 35.9
18" BEECH S75°E 16.43	10" MAPLE N48°W 35.54	6" OAK N60°E 27.5
7" MAPLE N60°E 27.15	12" Y. BIRCH S46°W 35.59	7" OAK S65°E 21.5
	N1/4 S-2 T26N, R12W. FD 5/8"	E-W TRAIL RD NORTH 10'±
U.S.M.C. S87°34'E 381.87	ROD W/RLS N87°51'W 36.04	
FD. PIPE W/G.L.O. CAP.	CAP #13030	

SIGNED BY Carl F. Roser DATE 02-03-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)
LONG LAKE TOWNSHIP
GRAND TRAVERSE COUNTY