

MAR 16 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in GRAND TRAVERSE (County)

Located In: Corner Code #

- 1. Public Land Survey T 27N R 11W D-9
2. Property Controlling in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

STATE OF MICHIGAN GRAND TRAVERSE COUNTY RECORDED

30 DEC 93 10:20 A.M.

KAREN ANDERSON REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 9.

I, Gary G. Wilson, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9: Original G.L.O. notes and witnesses. Act 74 filed by Robt. Mitchell in July, 1986 (Liber 3, Pg. 87) reports

concrete monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9: No physical evidence of the original GLO witnesses were found. Found homemade concrete monument (6" dia. concrete) with W. Batzer iron incased on old fence mound. Monument agrees with Mitchell's witnesses on his survey #86173.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9: 1/4 corner common to Sections 20 & 29 Perpetuated with 2-1/2" X 30" flanged bottom galvanized iron pipe with 3-1/2" brass cap stamped GRAND TRAVERSE COUNTY REMONUMENTATION.

- N15°E 16.44' Power Pole
S87°E 64.09' Power Pole
N51°W 52.77' 26" Maple
N64°E 52.79' 12" Maple

Corner approved by the Grand Traverse County Peer Review Group on 11-03-93.

Signed by Gary G. Wilson, PS
Surveyor's Michigan License No. 25881

Date December 28, 1993

